

HVAC System Assessment

SouthPark Centre - 4800 Sharon Road, Charlotte, NC

SYSTEM OVERVIEW

Report Date:	March 2026
Assessor:	Trane Technologies
System Type:	Rooftop Units (RTU)
Total Units:	8 RTUs
Original Install:	2001
Last Major Service:	2018 (compressor replacement on 2 units)

UNIT-BY-UNIT ASSESSMENT

RTU-1 (Fl 1-2):	Good	Replaced compressor 2018. 8-10 years remaining.
RTU-2 (Fl 1-2):	Good	Replaced compressor 2018. 8-10 years remaining.
RTU-3 (Fl 3):	Fair	Original unit. 2-3 years remaining. Budget for replacement.
RTU-4 (Fl 3-4):	Fair	Original unit. 2-3 years remaining. Budget for replacement.
RTU-5 (Fl 4-5):	Fair	Original unit. 3-4 years remaining. Budget for replacement.
RTU-6 (Fl 5-6):	Good	Refurbished 2020. 10+ years remaining.
RTU-7 (Fl 6-7):	Good	Refurbished 2020. 10+ years remaining.
RTU-8 (Fl 7-8):	Good	Refurbished 2020. 10+ years remaining.

RECOMMENDATIONS

Replace RTU-3, RTU-4, RTU-5:	\$180,000 total	Within 2-3 years. High-efficiency units recommended.
Preventive maintenance:	Current contract adequate	New Trane contract signed mid-2025.
Energy efficiency:	Consider VFD retrofit on older units	\$25,000 est. Optional.